



**ADDENDUM NO. ONE**

**ISSUE DATE: April 16, 2023**

**PROJECT: Def. Maint: Roads, Parking Lots, Sidewalks, Walkways – Roads & Lot E**  
**PROJECT NO.: H18-9584-MJ-B2**

---

**ADDENDUM SECTIONS:**

**RESPONSE TO PRE-BID QUESTIONS/NOTATIONS**

1. Contractor to mill 1.5"; not required to put a 789 stone on the tack coat after milling.
2. 6" Stone base will be required for full depth repair.
3. Compaction will be needed. All base and subgrade should be compacted to 100% modified proctor per ASTM D1557.
4. Pavement markings to all be 2 coats of alkyd traffic paint.
5. The University will not hold the Contractor responsible for tree damage following the cutting of the tree roots.
6. Contractor is required to coordinate with owner's third party inspectors as required throughout the project.

**QUESTIONS DEADLINE IS: Thursday, April 18 @ 5:00 PM**

**BID DUE DATE IS: Thursday, April 25 @ 2:00 PM**

**You must acknowledge receipt of all addenda on the appropriate line on the bid form.**